ABSTRACT OF THE DISCLOSURE

A gravel pack completion with fiber optic monitoring. In a described embodiment, a method for completing a subterranean well includes the steps of: positioning at least one assembly in a wellbore of the well; then inserting a portion of a tubular string into the assembly; and attaching a fiber optic line to the tubular string portion.